FI

Fraser...
Mount C
Ridgway
Smith's
On Line

Forrest .
Widder .
Park Hi
Ailsa Cr
Lucan ...
On Line

Forv

Wesh

GRAND TRUNK RAILWAY.

FIREWOOD required to be Delivered on WESTERN DISTRICT during the Winter of 1877-8.

Where to be Delivered.	No. of Cords.
DETROIT DIVISION.	
Fraser	2,000
Mount Clemens	2,000
Ridgway	2,500
Smith's Creek	4,500
On Line between Port Huron and Fraser	12,000
WESTERN DIVISION.	
Forrest	3,500
Widder	1,000
Park Hill	1 000
Ailsa Craig	4,000
Lucan	500
On Line between Ailsa Craig and Sarnia	14,500
Forward	47,500

Where to be Delivered.	No. of Cords.
Western Division—Continued.	
Forward	47,500
St. Mary's	4,000
Thorndale	500
Kelly's Siding and London Branch	5,000
BUFFALO AND GODERICH DIVISION.	
Goderich	2,000
Seaforth	100
Carronbrook	4,500
On Line between Stratford and Clinton	10,000
Bright	800
On Line between Bright and Stratford	3,000
Dunville	1,200
On Line between Caledonia and Bertie	4,000
Total	82,600

TENDER FOR FIREWOOD.

To

JOSEPH HICKSON, Esq.,

General Manager,

MONTREAL.

SIR,

.....hereby offer to supply the GRAND TRUNK RAILWAY COMPANY with .....Cords Hard Wood and.....Cords Soft Wood, conformable to the following specifications, to be delivered as follows:

_____ Station,_____Cords Hard Wood @_____℔ Cord,_____Cords Soft Wood, @_____℔ Cord

_____ " _____ " " _____ " _____ " " _____ "

_____ " _____ " " _____ " _____ " " _____ "

Signed, ...

SPECIFICATIONS OF CORDWOOD.

All wood must be split from the body of the tree, to average four feet long from scarp to point, no stick to be of unreasonable size, must be free from all crooked, crotched, or knotty sticks, and cut from growing trees, with the bark on; to be delivered at the places agreed upon, and there closely and evenly piled up in piles not less than eight feet high, and in all cases with the bark uppermost, and a space of three feet left between every two piles. Suitable stringers must be firmly laid on the ground; when necessary the snow must be removed for that purpose, and upon them the said Wood shall be piled. Piles which may, from the melting of the snow or any other cause, fall down before the final measurement is made, must be repiled. The final measurement shall not be made until the snow and ice have so far disappeared as to admit of its being correctly taken.

All Wood delivered with the bark off will only be received at a reduction of twenty-five per cent. from the prices specified.

Soft Wood must not be mixed with Hard Wood, but kept in distinct and separate piles, the one from the other; the ends of piles must be well headed up; and where said ends of piles are headed up with the wood laid crosswise, only half the measurement of the same will be allowed.

Wood that is piled more than four feet below the level of the track will not be accepted.

All Hard Wood must be cut from Hickory, White Oak, Hard Maple, Beech, Black Birch, or Ironwood.

All Soft Wood must be cut from Tamarac, Hemlock, Soft Maple, White Ash, Rock or Grey Elm.

The whole to be perfectly sound.